OFFICE OF THE PRINCIPAL
MAGADH MAHILA C OLLEGE COLLEGE
NORTH OF GANDHI MAIDAN
PATNA 800001
website:www.magadhmahilacollege.org, Telephone: 0612-2219454

EMERGENT NOTICE INVITING QUOTATION

Quotation No. P/MMC/179 Date 16-02-2026

NAME OF WORK: FIXING OF ALUMINIUM WINDOWS IN THE B.C.A. DEPARTMENT OF MAGADH MAHILA COLLEGE, P.U. PATNA

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition , please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M or website of College.

Designation of officer inviting quotation	Principal, Magadh Mahila College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal, Magadh Mahila College, Patna up to 3.00 p.m. on 10/03/2026.
Place, Time & Date of opening of quotation	Office of the Principal, Magadh Mahila College, Patna at 3.30 p.m. on 10/03/2026.

PRESCRIBED FORMAT

S.N	Code No	Description	Quantity		Unit	Rate (Rs.)	Amount (Rs.)
1		Desmantiling doors windows and clerestory windows (steel or wood) shutters including chowkhats, architrage, holdfasts etc. complete and stacking within 50 metres lead:					
a	15.12.	Of area 3 sqm and below	1	No	Each		
b	5.12.	Of area beyond 3 sqm	2	No	Each		
2		Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / aneling,C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately)					

P.K. 14/02/26

16-02-26 Principal
Magadh Mahila Coll
PATNA

Scanned with OKEN Scanner

S.N	Code No	Description	Quantity		Unit	Rate (Rs.)	Amount (Rs.)
a	21.1.1.2	For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)	46	Kg	Kg		
b	21.1.2.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately, Powder coated aluminium (minimum thickness of powder coating 50 micron)	46	Kg	Kg		
3	21.3.2	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5.50 mm thickness (weight not less than 12.50 kg/sqm)	12	Sqm	Sqm		
4	9.100.2	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade, with necessary screws etc. complete:100 mm	20	No	Each		
5	9.97.4	Providing and fixing aluminium tower bolts, IS Imarked, anodised (anodic coating not less than grade AC 10 as per IS:1868), transparent or dyed to required colour or shade, with necessary screws etc. complete:150x10 mm	25	No	Each		
6	9.48.2	Providing and fixing M.S.grills of required pattern in frames of windows etc. With M.S. flats, square or round bars etc. including priming coat with approved steel primer all completeFixed to openings/ wooden frames with rawl plugs screws etc	150	Kg	Kg		
7	13.93.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work.	12	Sqm	Sqm		

D.C.H/C
14/10/22

Scanned with OKEN Scanner

(23)

S.N	Code No	Description	Quantity		Unit	Rate (Rs.)	Amount (Rs.)
8		Reserved price for any other un seen work.	1	L.S.	L.S	739	739
		Total Amount					

TERMS & CONDITIONS:

1 Earnest Money Deposit in the form of Bank Draft in the favour of Principal, Magadh Mahila College, Patna or N.S.C./ Time Deposit of Post Office , duly pledged in the name of Principal, Magadh Mahila College, Patna @ 2% i.e.Rs.1680/- is essentilaly required with quotations. Remaining amount of Security Deposits @ 8% of bill amount will be deducted from bill.

2 The rate and amount of item vide serial number 8 has been fixed as Rs.739/- only.

3 Work must be completed within 45 days after receiving work order.

4 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.

5 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.

6 The undersignd reserve the right to accept or reject any or all the qootations without assigning any reason.

7 All disputes, what so ever shall be reffered to the sole arbitration of the Principal, Magadh Mahila College, Patna and his decision shall be final and binding on the agency.

16.12.26

PRINCIPAL,
MAGADH MAHILA COLLEGE, PATNA

Principal
Magadh Mahila College
PATNA

16/07/26

Scanned with OKEN Scanner