23

OFFICE OF THE PRINCIPAL
MAGADH MAHILA C OLLEGE COLLEGE
NORTH OF GANDHI MAIDAN

PATNA 800001

website:www.magadhmahilacollege.org, Telephone: 0612-2219454

EMERGENT NOTICE INVITING QUOTATION

Quotation No: P/MMC/180 Date 16-02-2026

NAME OF WORK: REPAIR AND PAINTING WORK IN THE DEPARTMENTS OF ZOOLOGY & HISTORY, MAGADH MAHILA COLLEGE, P.U. PATNA.

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition , please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M. or website of College.

Designation of officer inviting quotation	Principal, Magadh Mahila College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal, Magadh Mahila College, Patna up to 3.00 p.m. on 10/03/2026.
Place, Time & Date of opening of quotation	Office of the Principal, Magadh MahilaCollege, Patna at 3.30 p.m. on 10/03/2026.

PRESCRIBED FORMAT

S.N	Code No	Description	Quantity		Unit	Rate (Rs.)	Amount (Rs.)
1		Providing following materials of approved quality and workers for necessary work at roof, such as removal of existing water storage tank, refixing the water tank after constructin of a base for water tank, fixing over flow pipes, and repair of other rain water down pipes, as per direction of Engineer-in-charge.					
a	OL27	Plumber	4	Day	Day		
b	OL71	Skilled Labour	4	Day	Day		
c	7029	Galvanised wire mesh of average width of aperture 1.4 mm and romin 31 dia. of wire 0.63 mm	7	Sqm	Sqm		
d	8641	Chlorinated Polyvinyl - chloride (CPVC) pipe 50 mm outer dia	3	m	m		
e	1929	Brass full way valve with C.I. wheel (screwed end) 40 mm dia	2	No	Each		
2	6.1.1 2/1	Brick work with bricks of class designation 100 A in foundations and plinth in : Cement mortar 1 :4 (1 cement: 4 coarse sand)	0.2	Cum	Cum		
3	6.3A	Extra for Brick work in super structure above plinth level up to floor V cum	0.2	Cum	Cum		

PKM 14/03/26

16.02.2026
Principal
Magadh Mahila College
PATNA

Scanned with OKEN Scanner

22

S.N	Code No	Description	Quantity		Unit	Rate (Rs.)	Amount (Rs.)
4	4.2.2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars,post. struts, buttresses, string or lacing courses, parapets, coping ,bed blocks, anchor blocks, plian window sills, fillets etc.upto floor five level excluding the cost of centring, shuttering and finishing:1:1.5:3(1 Cement: 1:5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	1	Cum	Cum		
5	13.17.1.	12 mm cement plaster1:3 (1cement : 3 coarse sand) finished with a floating coat of neat cement	5	Sqm	Sqm		
6	11.38.	Providing and laying Ceramic glazed floor tiles 300 x 300 mm (thickness to be specified by the manufacturer) of ist quality conforming to IS: 15622 of approved make in colours such shades except white, Ivory, Grey, Fume Red, Brown, laid on 20 mm thick Cement motar 1:4 (1 cement :4 coarse sand) including pointing the joints with white cement and matching pigment etc., complete.	10	Sqm	Sqm		
7	18.18.3.	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete 25 mm nominal bore	1	No	Each		
8	18.7.4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot &cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at1.00 m spacing.This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.Internal work - Exposed on wall- 32 mm nominal outer dia Pipes	5	m	m		
9	0L71	Providing skilled labour for chisseling existing P.S. flooring work for re flooring, as per direction of Engineer-in-charge.	1	Day	Day		
10	11.41.2.	Providing and laying vitrifed floor tiles in different sizes (thickness to be specified bythemanufactruer) withwaterabsorption's less than 0.08% and conforming to IS : 15622 of approved make in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joint with white cement and matching pigments etc., complete.Size of Tile 60x60 cm	36	Sqm	Sqm		
11	15.56.	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	5	Sqm	Sqm		

PIGT
14/03/26

16.02.26
Principal
Magadh Mahila College
PATNA

Scanned with OKEN Scanner

S.N	Code No	Description	Quantity		Unit	Rate (Rs)	Amount (Rs)
12	11.46.2.	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), withwater absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), including grouting the joint with white cement & matching pigments etc. complete.Size of Tile 600 x 600 mm.	5	Sqm	Sqm		
13		Providing following materials of approved quality for covering expansion joints and dismantling wall for proposed ventilators, as per direction of Engineer-in-charge					
a	2631	A.C.P. of 4 mm thickness	10	Sqm	Sqm		
b	OL71	Skilled Labour	8	Lab/Day	Lab/Day		
c	o458	plastic sleeves for screw	130	No	Each		
d	o635	Brigh finish or black enameled mild steel screws 50 mm	130	No	% no		
14	14.1.2	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.With cement mortar 1:4 (1cement: 4 coarse sand)	25	Sqm	Sqm		
15	13.80.	Removing dry or oil bound distemper by scrapping, sand paper and preparing the surface smooth including necessary repari scratches etc. complete.	269	Sqm	Sqm		
16	13.80 A.1.	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	294	Sqm	Sqm		
17	13.46.	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	294	Sqm	Sqm		
18	13.93.1.	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work	49	Sqm	Sqm		
19	9.21.2	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (PartI) non-decorative type, coreof block board construction with frame of 1 st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	1.6	Sqm	Sqm		

16.12.26
Principal
...th Mahila Colleg...
...TNA

Scanned with OKEN Scanner

S.N.	Code No	Description	Quantity		Unit	Rate (Rs)	Amount (Rs)
20	9.97.4	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyedto required colour or shade, with necessary screws etc. complete: 150x10 mm	1	No	Each		
21	9.100.2	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete: 100 mm	2	No	Each		
22	9.96.2.	Providing and fixing aluminium sliding door bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete: 250x16 mm	1	No	Each		
23		Carriage of materials					
a		Designation 100 A bricks from 8 Km distance of surface road with an additional lead of 1 Km lead of kutcha road.	82	No	%0No		
b		Stone aggregate from Manpur, Gaya 100 km distance	1	Cum	Cum		
c		Sone sand from Koelwar, 45 Km distance of surface road.	3	Cum	Cum		
24	S.O.R.	Price difference of materials for Patna urban area.					
a		Designation 100 A bricks .	82	No	%0No		
b		Cement	25	Bag	Bag		
25		Reserve price for any other unseen work.	1	L.S.	L.S.	4476	4476
		Total Amount					

TERMS & CONDITIONS:

1 Earnest Money Deposit in the form of Bank Draft in the favour of Principal, Magadh Mahila College, Patna or N.S.C./ Time Deposit of Post Office , duly pledged in the name of Principal, Magadh Mahila College, Patna @ 2% i.e.Rs.4000/- is essentilaly required with quotations. Remaining amount of Security Deposits @ 8% of bill amount will be deducted from bill.

2 The rate and amount of item vide serial number 25 has been fixed as Rs.4476/- only.

3 Work shall be completed within 45 days after receiving work order.

4 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.

5 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.

6 The undersignd reserve the right to accept or reject any or all the qootations without assigning any reason.

7 All disputes, what so ever shall be reffered to the sole arbitration of the Principal, Magadh Mahila College, Patna and his decision shall be final and binding on the agency

16.12.26

Principal
Magadh Mahila College
PATNA

PRINCIPAL,
MAGADH MAHILA COLLEGE, PATNA

16/02/2026

Scanned with OKEN Scanner